

Schedule of Rate

Name of work: Inside & outside Painting & minor repairing work at A.P.J Abdul Kalam PG Hostel (D-type qtr) NIT Silchar. Block: A, B & C

Completion period: 60 days.

OR:-

CR:-

OM:-

Sl. No.	Description of Item	Unit	Quantity	Rate in fig	Rate in word	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30cm in depth. 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50m and lift upto 1.5m, disposed earth to be levelled and neatly dressed. All kind of soil	Cum	5.00			
2	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. In cement mortar	Cum	5.00			
3	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	Cum	1.00			
4	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead : Of area 3 sq. metres and below	Each	5.00			
5	Taking out doors, windows and clerestory window shutters (steel or wood) including stacking within 50 metres lead : Of area 3 sq. metres and below	Each	5.00			
6	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :					
	1:1½:3 (1 Cement: 1½ coarse sand: 3 graded stone aggregate 20 mm nominal size)	Cum	1.00			

OR:-
CR:-
OM:-

Sl. No.	Description of Item	Unit	Quantity	Rate in fig	Rate in word	Amount
	1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 20mm nominal size)	Cum	1.00			
7	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement, with 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) : 3 graded stone aggregate 20 mm nominal size)	Cum	1.00			
8	Centering and shuttering including strutting, propping etc. and removal of form for : Suspended floors, roofs, landings, balconies and access platform	Sqm	15.00			
9	Centering and shuttering including strutting, propping etc. and removal of form for : Weather shade, Chajjas, corbels etc., including edges	Sqm	15.00			
10	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above. Thermo-Mechanically Treated bars of grade Fe-500 D or more.	Kg	50.00			
12	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:4 (1 cement : 4 coarse sand)	Cum	0.50			
13	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level. Cement mortar 1:4 (1 cement : 4 coarse sand)	Sqm	15.00			
14	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete. Fixed to steel windows by welding	Kg	250.00			

OR:-
CR:-
OM:-

Sl. No.	Description of Item	Unit	Quantity	Rate in fig	Rate in word	Amount
15	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately). Sal wood	Cum	0.25			
16	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) non-decorative type, core of block board construction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters: 30 mm thick including ISI marked Stainless Steel butt hinges with necessary screws	Sqm	15.00			
17	Providing and fixing oxidised M.S. casement stays (straight peg type) with necessary screws etc. complete. 300 mm weighing not less than 200 gms	Each	30.00			
18	Supplying, fitting, fixing anodised aluminium fittings of approved make, resonably smooth, free from sharp edges and corners, flaws and other defects and with counter sunk holes for screws including necessary aluminium screws etc. complete.(anodised to bright natural matt & satin finished)					
	a) Sliding door bolts - 300x16 mm	each	10.00			
	b) Tower bolts - 250x10 mm	each	10.00			
	c) Tower bolts 150mm x 10mm	each	10.00			
	d) Door handles iii) 125mm	each	10.00			

OR:-
CR:-
OM:-

Sl. No.	Description of Item	Unit	Quantity	Rate in fig	Rate in word	Amount
19	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	Kg	50.00			
20	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS:15622 (thickness to be specified by the manufacturer) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-charge in skirting, risers of steps and dados over 12mm thick bed of cement mortar 1 : 3 (1 cement : 3 fine sand) and jointing with grey cement slurry @ 3.3 kg per sqm including pointing in white cement mixed with pigment of matching shade complete.	Sqm	75.00			
21	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick bed of cement mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ 3.3kg/sqm including pointing the joints with white cement and matching pigments etc., complete.	Sqm	45.00			
22	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes.					
	75 mm diameter	Rmt	20.00			
	110 mm diameter	Rmt	30.00			
	Providing and fixing on wall face unplasticised - PVC moulded fittings/accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion.					
	(a) Coupler					

OR:-
CR:-
OM:-

Sl. No.	Description of Item	Unit	Quantity	Rate in fig	Rate in word	Amount
23	75 mm diameter	Each	3.00			
	110 mm diameter	Each	3.00			
	(b) Single tee with door					
	75x75x75 mm	Each	3.00			
	110x110x110 mm	Each	3.00			
	(c) Single tee without door					
	75x75x75 mm	Each	3.00			
	110x110x110 mm	Each	3.00			
	(d) Bend 87.5°					
24	75 mm diameter	Each	3.00			
	110 mm diameter	Each	3.00			
	Providing and fixing unplasticised -PVC pipe clips of approved design to unplasticised - PVC rain water pipes by means of 50x50x50 mm hard wood plugs, screwed with M.S. screws of required length, including cutting brick work and fixing in cement mortar 1:4 (1 cement : 4 coarse sand) and making good the wall etc. complete.					
	75mm	Each	5.00			

OR:-
CR:-
OM:-

Sl. No.	Description of Item	Unit	Quantity	Rate in fig	Rate in word	Amount
	110mm	Each	10.00			
25	15 mm cement plaster on rough side of single or half brick wall finished with a floating coat of neat cement of mix : 1 : 4 (1 cement : 4 fine sand)	Sqm	25.00			
26	6 mm cement plaster 1 : 3 (1 cement : 3 fine sand)	Sqm	50.00			
27	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	Sqm	6800.00			
28	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface : Water thinnable cement primer	Sqm	6800.00			
29	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade : Old work (one or more coats)	Sqm	3850.00			
30	Finishing walls with Acrylic Smooth exterior paint of required shade: Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface	Sqm	2950.00			
31	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work	Sqm	1300.00			

OR:-
CR:-
OM:-

Sl. No.	Description of Item	Unit	Quantity	Rate in fig	Rate in word	Amount
32	Applying priming coat: With ready mixed pink or Grey primer of approved brand and manufacture on wood work (hard and soft wood)	Sqm	30.00			
33	With ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel galvanised iron/ steel works	Sqm	30.00			
34	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	Sqm	30.00			
35	Re-lettering with black Japan paint of approved brand and manufacture	Per letter per cm height	1500.00			
36	Hacking of CC flooring including cleaning for surface etc. complete as per direction of the Engineer-in-Charge.	Sqm	50.00			
37	Dismantling 15 to 40 mm dia G.I. pipe including stacking of dismantled pipes within 50 metres lead as per direction of Engineer- in-Charge. (a) Internal Work - Exposed on wall	Rmt	100.00			
38	Taking out existing wooden door shutter, repair by cutting, painting etc. and refixing of repaired door shutters to existing door frames, including replacement of hinges with screws, etc. as required, all complete as per the direction of the Engineer-in-charge.	Each	5.00			

OR:-
CR:-
OM:-

Sl. No.	Description of Item	Unit	Quantity	Rate in fig	Rate in word	Amount
39	Providing and fixing water closet squatting pan (Indian type W.C. pan) with 100 mm sand cast Iron P or S trap, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required: White Vitreous china Orissa pattern W.C. pan of size 580x440 mm with integral	Each	4.00			
40	Providing and fixing mirror of superior glass (of approved quality) and of required shape and size with plastic moulded frame of approved make and shade with 6 mm thick hard board backing : Circular shape 450 mm dia	Each	10.00			
41	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. Internal work - Exposed on wall					
	15 mm nominal outer dia Pipes	Rmt	5.00			
	20 mm nominal outer dia Pipes	Rmt	80.00			
	25 mm nominal outer dia Pipes	Rmt	10.00			
	32 mm nominal outer dia Pipes	Rmt	30.00			
	40 mm nominal outer dia Pipes	Rmt	60.00			

OR:-
CR:-
OM:-

Sl. No.	Description of Item	Unit	Quantity	Rate in fig	Rate in word	Amount
42	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. External work					
	15 mm nominal outer dia Pipes	Rmt	5.00			
	20 mm nominal outer dia Pipes	Rmt	40.00			
	25 mm nominal outer dia Pipes	Rmt	10.00			
	32 mm nominal outer dia Pipes	Rmt	30.00			
	40 mm nominal outer dia Pipes	Rmt	60.00			
43	Constructing masonry Chamber 30x30x50 cm inside, in brick work in cement mortar 1:4 (1 cement :4 coarse sand) for stop cock, with C. I. surface box 100x100 x75 mm (inside) with hinged cover fixed in cement concrete slab 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size), i/c necessary excavation, foundation concrete 1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40mm nominal size) and inside plastering with cement mortar 1:3 (1 cement : 3 coarse sand) 12mm thick, finished with a floating coat of neat cement complete as per standard design : With common burnt clay F.P.S.(non modular) bricks of class designation 7.5	Each	3.00			

OR:-
CR:-
OM:-

Sl. No.	Description of Item	Unit	Quantity	Rate in fig	Rate in word	Amount
44	Providing and fixing PVC Door Frame of size 50x47 mm with a wall thickness of 5 mm (\pm 0.2 mm), made out of single piece extruded PVC profile, with mitred cut joints and joint with 2 nos of PVC bracket of size 190 mm x 100 mm long arms of cross section size 35 x 15 mm & self driven self tapping screws, the vertical door profiles to be reinforced with 40x20 mm M.S. rectangular tube of 0.8 mm , including providing EPDM rubber gasket weather seal throughout the frame, including jointing 5 mm PVC frame strip with PVC solvent cement on the back of the profile. The door frame to be fixed to the wall using 8 x100 mm long anchor fasteners complete, all as per manufacturer's specification and direction of Engineer -in- charge.	Meter	20.00			
45	30 mm thick factory made Polyvinyl Chloride (PVC) door shutter made of styles and rails of a uPVC hollow section of size 60x30 mm and wall thickness 2 mm (\pm 0.2 mm), with inbuilt decorative moulding edging on one side. The styles and rails mitred and joint at the corners by means of M.S. galvanised/ plastic brackets of size 75x220 mm having wall thickness 1.0 mm and stainless steel screws. The styles of the shutter reinforced by inserting galvanised M.S. tube of size 25x20 mm and 1mm (\pm 0.1 mm) wall thickness. The lock rail made up of 'H' section, a uPVC hollow section of size 100x30 mm and 2 mm (\pm 0.2 mm) wall thickness fixed to the shutter styles by means of plastic/ galvanised M.S. 'U' cleats. The shutter frame filled with a uPVC multi-chambered single panel of size not less than 620 mm, having over all thickness of 20 mm and 1 mm (\pm 0.1 mm) wall thickness . The panels filled vertically and tie bar at two places by inserting horizontally 6 mm galvanised M.S. rod and fastened with nuts and washers, complete as per manufacturer's specification and direction of Engineer-in-charge.	Sqm	8.00			
46	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground within 50 metres lead : With cement mortar 1:4 (1 cement: 4 coarse sand)	Sqm	100.00			
47	Renewing glass panes, with putty and nails wherever necessary including racking out the old putty; Float glass panes of thickness 4 mm	Sqm	75.00			

OR:-
CR:-
OM:-

Sl. No.	Description of Item	Unit	Quantity	Rate in fig	Rate in word	Amount
48	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require : White Vitreous China Wash basin size 630x450 mm with a pair of 15 mm C.P. brass pillar taps	Each	3.00			
49	Providing and fixing C.P. brass bib cock of approved quality conforming to IS:8931 : 15 mm nominal bore	Each	10.00			
50	Providing and fixing brass stop cock of approved quality : 15 mm nominal bore	Each	10.00			
51	Providing and laying water proofing treatment to vertical and horizontal surfaces of depressed portions of W.C., Kitchen and the like consisting of : i) Ist course of applying cement slurry @ 4.4 Kg / sqm mixed with water proofing compound conforming to IS 2645 in recommended proportions including rounding off junction of vertical and horizontal surface. ii) IInd course of 20 mm cement plaster 1 : 3 (1 cement : 3 coarse sand) mixed with water proofing compound in recommended proportion including rounding off junction of vertical and horizontal surface. iii) IIIrd course of applying blown or residual bitumen applied hot at 1.7 kg per sqm of area. iv) IVth course of 400 micron thick PVC sheet. (Overlaps at joints of PVC sheet should be 100 mm wide and pasted to each other with bitumen @ 1.7 Kg / sqm.	Sqm	20.00			

Total = Rs.
Unconditional Rebate (if any) = Rs.
Net Total = Rs.

Rupees